

Tarife pentru lucrarile de amenajare, intretinere si infrumusetare spatii verzi

NR CRT	SIMBOL LUCRARE	DENUMIRE LUCRARE	UM	Tarif orar	Norma	Cheltuieli angajator	Cota de concediu angajator	PRET
1	TSH17B1	Saparea manuala a gropilor pentru plantat pomi	MP	11,48	1,8	1,0225	1,08	22,82
2	TSH18C1	Extragerea manuala a puietilor in vederea plantatului	BUC	11,48	0,41	1,0225	1,08	5,20
3	TSH24C1	Plantat puieti de arbori foiosi fara balot	BUC	11,48	1,057	1,0225	1,08	13,40
4	TSH25A1	Transplantari cu balot la arbusti	ORE	11,48	1,48	1,0225	1,08	18,76
5	TSH01A1	Degajarea terenului de corpuri straine	MP	11,48	7,07	1,0225	1,08	89,63
6	TSH2A1	Taierea manuala a arborilor prin sectionare succesiva a arborilor cu diametru mai mic de 20 cm	BUC	11,48	0,46	1,0225	1,08	5,83
7	TSH2B	Taierea manuala a arborilor prin sectionare succesiva a arborilor cu diametru 11-30 cm	BUC	11,48	12,24	1,0225	1,08	155,17
8	TSH03A1	Extragerea pamantului teren mijlociu	MP	11,48	0,98	1,0225	1,08	12,42
9	TSH03B1	Extragerea pamantului pt aranjat spatii verzi, teren tare	MP	11,48	1,77	1,0225	1,08	22,44
10	TSH04A1	Mobilizare manuala a solului in teren mijlociu adancime 10 cm	MP	11,48	0,19	1,0225	1,08	2,41
11	HSH04B1	Mobilizare manuala a solului in teren mijlociu adancime 20 cm	MP	11,48	0,27	1,0225	1,08	3,42
12	TSH04C1	Mobilizare manuala a solului in teren mijlociu adancime 30 cm	MP	11,48	0,35	1,0225	1,08	4,44
13	TSH05A1	Asternere pamant vegetal grosime 10 cm	MP	11,48	0,11	1,0225	1,08	1,39
14	TSH05B1	Asternere pamant vegetal grosime 15 cm	MP	11,48	0,13	1,0225	1,08	1,65
15	TSH05C1	Asternere pamant vegetal grosime 20 cm	MP	11,48	0,14	1,0225	1,08	1,77
16	TSH5D1	Asternere pamant vegetal grosime 30 cm	MP	11,48	0,18	1,0225	1,08	2,28
17	TSH09A1	Semanat gazon	100mp	11,48	4,82	1,0225	1,08	61,10
18	TSH12A+B	Udat suprafete cu furtunul	100mp	11,48	0,386	1,0225	1,08	4,89
19	TSH13BHR	Administrarea ingrasamintelor chimice	TONE	11,48	80,37	1,0225	1,08	1018,88
20	TSH14A1	Cosit manual gazon	100mp	11,48	0,813	1,0225	1,08	10,31
21	TSH15A1	Plivit manual buruieni din peluze	100mp	11,48	2,533	1,0225	1,08	32,11
22	TSH16A1	Rectificat margini la peluze si rabate	100mp	11,48	2,57	1,0225	1,08	32,58

Tarife pentru lucrarile de amenajare, intretinere si infrumusetare spatii verzi

23	TSH17B1	Sapat gropi poligonale in teren mijlociu	MC	11,48	1,08	1,0225	1,08	13,69
24	TSH17C1	Sapat gropi poligonale in teren TARE	MC	11,48	2,753	1,0225	1,08	34,90
25	TSH18B1	Extragere arbusti cu ghimpi si trandafiri	BUC	11,48	0,39	1,0225	1,08	4,94
26	TSH24A1	Plantat arbusti fara balot de pamant	BUC	11,48	0,357	1,0225	1,08	4,53
27	TSH24B1	Plantat trandafiri, arbusti cu ghimpi fara balot de pamant	BUC	11,48	0,515	1,0225	1,08	6,53
28	TSH26A1	Plantat gard viu, rasinosi pe un rand	ML	11,48	0,57	1,0225	1,08	7,23
29	TSH26B1	Plantat gard viu, rasinosi pe 2 randuri	ML	11,48	0,96	1,0225	1,08	12,17
30	TSH26E1	Plantat gard viu BUXUSi pe un rand	ML	11,48	0,285	1,0225	1,08	3,61
31	TSH26F1	Plantat gard viu BUXUSi pe 2 randuri	ML	11,48	0,564	1,0225	1,08	7,15
32	TSH27A1	Udat plantatii cu furtunul	MP	11,48	0,855	1,0225	1,08	10,84
33	TSH27B1	Udat plantatii cu galeata	100mp	11,48	4,275	1,0225	1,08	54,20
34	TSH28A1	Taieri de corectie la arbori cu inaltimea mai mica de 7 m	BUC	11,48	0,561	1,0225	1,08	7,11
35	TSH28B1	Taieri de corectie la arbori cu inaltimea peste 7 m	BUC	11,48	0,779	1,0225	1,08	9,88
36	TSH28C1	Taieri de regenerare trandafiri	BUC	11,48	0,067	1,0225	1,08	0,85
37	TSH29A1	Tuns gard viu inaltime sub 1,2 m	MP	11,48	0,029	1,0225	1,08	0,37
38	TSH29B1	Tuns gard viu inaltime peste 1,2 m	MP	11,48	0,048	1,0225	1,08	0,61
39	TSH29C1	Tuns borduri si chenare de BUXUS	MP	11,48	0,143	1,0225	1,08	1,81
40	TSH30A1	Plantat flori cu inaltimea mai mica de 15 cm	100mp	11,48	2,529	1,0225	1,08	32,06
41	TSH30C1	Plantat flori in jardiniere si vase decorative	100 BUC	11,48	3,848	1,0225	1,08	48,78
42	TSH31A1	Combaterea bolilor si daunatorilor prin stropire	100 BUC	11,48	16,3	1,0225	1,08	206,64
43	TSH31B1	Combaterea bolilor si daunatorilor prin prafuire	100 BUC	11,48	18,04	1,0225	1,08	228,70
44	TSG1A1	Degajarea terenului de frunze si crengi	100mp	11,48	1,62	1,0225	1,08	20,54
45	TSG3B1	Defrisarea manuala tufisuri, arbusti, scoaterea radacinilor	100mp	11,48	10,26	1,0225	1,08	130,07
46	TDG14A1	Cosit vegetatie ierboasa	100mp	11,48	0,62	1,0225	1,08	7,86
47	NL	Curatit fantana arteziana, paza parc, reparatii instalatii de irigat, diverse aranjamente florale si ornamentale	ORE	11,48	ore regie	1,0225	1,08	#VALUE!
48	NL	Carat gunoi cu cosul (gazon rezultat in urma taierii) peste 50 m	TONE	11,48	2,93 ?	1,0225	1,08	37,14
49	NL	Carat gunoi cu cosul (gazon rezultat in urma taierii) la 20 m	TONE	11,48	1,55 ?	1,0225	1,08	19,65
50	NL	Combaterea bolilor si daunatorilor cu pompa VERMOREL	100mp	11,48	0,59	1,0225	1,08	7,48
51	NL	Spalat manual cu furtunul	1000mp	11,48	0,64	1,0225	1,08	8,11

Tarife pentru lucrarile de amenajare, intretinere si infrumusetare spatii verzi

50	NL	Combaterea bolilor si daunatorilor cu pompa VERMOREL	100mp	11,48	0,59	1,0225	1,08	7,48
51	NL	Spalat manual cu furtunul	1000mp	11,48	0,64	1,0225	1,08	8,11
52	NL	Taieri de regenerare la garduri vii	ML	11,48	0,57	1,0225	1,08	7,23
53	NL	Taiat flori uscate	100 BUC	11,48	2,74	1,0225	1,08	34,74
54	NL	Varuit arbori cu diametrul mai mic de 10 cm	BUC	11,48	0,075	1,0225	1,08	0,95
55	NL	Varuit arbori cu diametrul 11-30 cm	BUC	11,48	0,113	1,0225	1,08	1,43
56	NL	Varuit arbori cu diametrul peste 30 cm	BUC	11,48	0,2	1,0225	1,08	2,54
57	NL	Udat jardiniere mici	BUC	11,48	0,04	1,0225	1,08	0,51
58	NL	Plivit jardiniere	BUC	11,48	0,17	1,0225	1,08	2,16
59	NL	Cosit suprafete cu cositoarea STIHL	100mp	11,48	1,1	1,0225	1,08	13,95
60	NL	Cosit suprafete cu tractoras HUSQVARNA	100mp	11,48	0,18	1,0225	1,08	2,28
61	NL	Cosit suprafete cu tractoras Hf	100mp	11,48	0,197	1,0225	1,08	2,50
62	NL	Spart gheata manual grosime 3cm	MP	11,48	0,09	1,0225	1,08	1,14
63	NL	Spart gheata manual grosime 3-5 cm	MP	11,48	0,116	1,0225	1,08	1,47
64	NL	Spart gheata manual grosime 5-7 cm	MP	11,48	0,176	1,0225	1,08	2,23
65	NL	Spart gheata manual grosime peste 7 cm	MP	11,48	0,25	1,0225	1,08	3,17
66	NL	Tratamente cu atomizorul	100mp	11,48	0,61	1,0225	1,08	7,73
67	NL	Maturat suprafete cu turbina de aer	100mp	11,48	0,102	1,0225	1,08	1,29
68	NL	Sapat suprafete cu motosapa	100mp	11,48	0,3	1,0225	1,08	3,80
69	NL	Tuns gard viu cu masina de tuns gard	MP	11,48	0,063	1,0225	1,08	0,80
70	NL	Tuns suprafete cu masina de tuns gazon	100mp	11,48	1,025	1,0225	1,08	12,99
71	NR43	Curatirea terenului de arborete cu motofierastraul	100mp	11,48	1,4	1,0225	1,08	17,75
72	NR45	Doborarea arborilor cu motofierastraul	BUC	11,48	3,1	1,0225	1,08	39,30

Director
Chitu Elena



Chitu Elena